BRUHAT BANGALORE MAHANAGARA PALIKE

3BMP/2016-17/RD/WORK_INDENT24200/CALL-:

APPROVED SCHEDULE - B

/BTP/BBMP/E-PMT/21/2016-17, Date: 14.02.2017

xtention of Major culvert at singapura main road near ward office in ward no 11 (Kuvempunagar) in Vidyaranyapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH	
				In Figures	In Words
1	33.93	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled materials, disposal of unserviceable material and stacking the serviceable material with all lifts and lead and lead of 10000 meters complete as per specifications. lime/cement concrete, I.by manual means B. cement concrete grade M-15 & M-20 etc complete as per specifications and directions of engineer in charge of the work	Cum	380.4	Rupees Three Hundred Eighty and Forty Paise Only
2	486	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	396.0	Rupees Three Hundred Ninety Six Only
3	54.68	Providing and filling in foundation with granite/trap broken metal 100mm, and down size, with approved sand including had packing, ramming, watering, including cost of all materials and labour with all lead and lift, etc complete as per specifications and directions of engineer in charge of the work	Cum	2163.16	Rupees Two Thousand One Hundred Sixty Three and Sixteen Paise Only
4	24.3	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5210.73	Rupees Five Thousand Two Hundred Ten and Seventy Three Paise Only
5	204.88	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete for R.C.C works laid in 15cms thick layers and well compacted vibrating curing etc. including smooth finish in CM 1:3,with all lead and lift etc., complete. (exclusive of cost of steel and fabrication charges) Ready mixed Cement concrete for Beams, column, Staircase and Roof with M-25 (1:1:2) (Cement - 399 Kg/Cum) etc complete as per specifications and directions of engineer in charge of the work	Cum	5210.73	Rupees Five Thousand Two Hundred Ten and Seventy Three Paise Only
6	20.49	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	59031.27	Rupees Fifty Nine Thousand Thirty One and Twenty Seven Paise Only
7	319.98	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	305.18	Rupees Three Hundred Five and Eighteen Paise Only
8	202.5	Construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murrum, watering charges & compaction by vibratory roller) etc complete as per specifications and directions of engineer in charge of the work	Cum	309.48	Rupees Three Hundred Nine and Forty Eight Paise Only

Signature of the contractor

Executive Engineer

07/07

	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH	
				In Figures	In Words
9	15	Providing and laying reinforced cement concrete pipe NP3 for culverts including pointing ends, and fixing collars with cement mortar 1:2 including cost of all materials, labour, curing complete as per specifications, 750 mm etc complete as per specifications and directions of engineer in charge of the work	M	4363.95	Rupees Four Thousand Three Hundred Sixty Three and Ninety Five Paise Only

U. Ramesh
Signature of the Contractor

Executive Engineer 7/07
Byarayanapura Division
BBMP, Bangalore - 92
07/07